PROGRAMMATIC COST ESTIMATE	FORELLA GROUP, LLC	Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Proj Name: NEW ABINGDON E.S.	9495 Silver King Court	Approved By:	pf	File:	Programmatic	
Project Owner: Arlington Public Schools	Suite A			Email:	Design	
Project Location: Arlington County, VA	Fairfax, VA 22031-4713			Report Date:	Reference Date Stamp	

Scheme and	Uniformat System Heading	Uniformat	Descriptions and/or Specification Notes	Computed	Unit of	Mat+Lab+Equip	Line Extension	Subtotals

COST SUMMARY

Summary	BASELINE HARD COSTS	ABINGDON ES NEW	92,000.00	GSF	215.57	19,832,632.20	
Summary		SCHOOL BUILDING SITE WORK	1.00	LS		3,380,802.19	
Summary		SUBTOTAL					23,213,434.39
Summary							
Summary	CONTINGENCIES	DESIGN CONTINGENCY		[15%]		3,482,015.16	
Summary		SUBTOTAL				26,695,449.55	
Summary		CHANGE ORDER CONTINGENCY		[5%]		1,334,772.48	
Summary		SUBTOTAL					28,030,222.03
Summary							
Summary	SOFT COSTS	COUNTY SOFT COST FACTOR		[22.5%]		6,306,799.96	
Summary		SUBTOTAL					34,337,021.98
Summary							
Summary	ESCALATED TOTALS	TOTAL, 2011		Current Dollars		34,337,021.98	
Summary		TOTAL, 2012		Esc to: 06/30 at 4%		35,710,502.86	
Summary		TOTAL, 2013		Esc to: 06/30 at 4%		37,138,922.98	
Summary		TOTAL, 2014		Esc to: 06/30 at 4%		38,624,479.90	
Summary		TOTAL, 2015		Esc to: 06/30 at 4%		40,169,459.09	
Summary		TOTAL, 2016		Esc to: 06/30 at 4%		41,776,237.46	
Summary							
Summary	PROGRAM TOTAL	SELECTED YEAR					41,776,237.46
Summary							
Summary							
Summary					Includes GC OH&P		Incl All Contingencies, Soft Costs
Summary	ALTERNATES						

PROGRAMMATIC COST ESTIMATE			FORELLA GROUP, LLC	Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Proj Name: NEW ABINGDON E.S.			9495 Silver King Court	Approved By:	pf	File:	Programmatic	
Project Owner: Arlington Public Schools			Suite A			Email:	Design	
Project Location: Arlington County, VA			Fairfax, VA 22031-4713			Report Date:	Reference Date Stamp	

Scheme and Location Ref	Uniformat System Heading	Uniformat No. Code		Descriptions and/or Specification Notes	Computed Quantity [US]	Unit of Meas	Mat+Lab+Equip Loaded Unit	Line Extension	Subtotals

COST SUMMARY ECC

ECC Summary	ECC HARD COSTS	ECC NEW BUILDING	39,000.00	GSF	200.65	7,825,173.32
ECC Summary		ECC SITE WORK	1.00	LS		1,258,755.50
ECC Summary						

PROGRAMMATIC COST ESTIMATE		FORELLA GROUP, LLC	Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Proj Name: NEW ABINGDON E.S.		9495 Silver King Court	Approved By:	pf	File:	Programmatic	
Project Owner: Arlington Public Schools		Suite A			Email:	Design	
Project Location: Arlington County, VA		Fairfax, VA 22031-4713			Report Date:	Reference Date Stamp	

Scheme and Location Ref	Uniformat System Heading	Uniformat No. Code	Descriptions and/or Specification Notes	Computed Quantity [US]	Unit of Meas	Mat+Lab+Equip Loaded Unit	Line Extension	Subtotals
			CLASSROOM ADDITION					
A	SUBSTRUCTURE	0.00	***System Subtotal***	92,000.00	GSF	3.57		328,384.59
				1,673.00	Perim			
New ES			***Lower Level Assemblies***					
New ES		1.00	Concrete spread footing foundations	154.91	CY	350.00	54,217.59	
New ES		2.00	Foundation drainage	1,773.00	LF	20.00	35,460.00	
New ES		3.00	Concrete slabs on grade	34,101.00	SF	7.00	238,707.00	
B	SHELL		***System Subtotal***	92,000.00		65.98		6,070,054.84
New ES			***Supported Floor Structure***					
New ES		1.00	Supported floor frame & columns	289.50	Tons	2,700.00	781,636.50	
New ES		2.00	Metal deck assembly	66,583.85	SF	2.50	166,459.63	
New ES		3.00	Slab on deck	57,899.00	SF	4.00	231,596.00	
New ES		4.00	Fireproofing	57,899.00	SF	0.25	14,474.75	
New ES								
New ES			***Roof Structure***					
New ES		1.00	Roof: Horizontal steel framing & columns	173.70	Tons	2,700.00	468,981.90	
New ES		2.00	Roof: Metal deck incl lapping & wastage	66,583.85	SF	2.25	149,813.66	
New ES		5.00	Fireproofing	92,000.00	GSF	0.25	23,000.00	
New ES								
New ES			***Miscellaneous Metals***					
New ES		1.00	Stairs		Ref Stairs & Railings, below			
New ES		2.00	Miscellaneous fabrications	92,000.00	SF	2.00	184,000.00	
New ES		3.00	Expansion jts assemblies & covers	92,000.00	SF	0.19	17,130.40	
New ES								
New ES			***Exterior Enclosure Assemblies***					
New ES		1.00	Exterior Wall System #1	56,280.00	Wall SF	30.00	1,688,400.00	
New ES		2.00	Exterior Wall System #2	0.00	Wall SF	0.00	0.00	
New ES		3.00	Exterior Wall System #3	0.00	Wall SF	0.00	0.00	
New ES		4.00	Modifications at Connection to Ex Bldg	4.00	EA	25,000.00	100,000.00	
New ES								
New ES			***Exterior Fenestration Assemblies***					
New ES		1.00	Fenestration System	18,760.00	SF	40.00	750,400.00	

PROGRAMMATIC COST ESTIMATE			FORELLA GROUP, LLC	Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Proj Name: NEW ABINGDON E.S.			9495 Silver King Court	Approved By:	pf	File:	Programmatic	
Project Owner: Arlington Public Schools			Suite A			Email:	Design	
Project Location: Arlington County, VA			Fairfax, VA 22031-4713			Report Date:	Reference Date Stamp	

Scheme and Location Ref	Uniformat System Heading	Uniformat No. Code	Descriptions and/or Specification Notes	Computed Quantity [US]	Unit of Meas	Mat+Lab+Equip Loaded Unit	Line Extension	Subtotals
New ES								
New ES			***Exterior Door Assemblies***					
New ES		1.00	Exterior storefront door assemblies, double	6.00	Pair	3,000.00	18,000.00	
New ES		2.00	Exterior storefront door assemblies, single	3.00	Leaf	1,000.00	3,000.00	
New ES		3.00	Exterior metal door assemblies, double	4.00	Pair	1,500.00	6,000.00	
New ES		4.00	Exterior metal door assemblies, single	3.00	Leafs	1,000.00	3,000.00	
New ES		5.00	Interior OH Doors	2.00	EA	3,500.00	7,000.00	
New ES								
New ES			***Roofing Assemblies***					
New ES		1.00	Membrane, insul., flashing, accessories	92,000.00	SF	15.00	1,380,000.00	
New ES		2.00	Blocking	92,000.00	GSF	0.27	24,472.00	

PROGRAMMATIC COST ESTIMATE			FORELLA GROUP, LLC	Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Proj Name: NEW ABINGDON E.S.			9495 Silver King Court	Approved By:	pf	File:	Programmatic	
Project Owner: Arlington Public Schools			Suite A			Email:	Design	
Project Location: Arlington County, VA			Fairfax, VA 22031-4713			Report Date:	Reference Date Stamp	

Scheme and Location Ref	Uniformat System Heading	Uniformat No. Code	Descriptions and/or Specification Notes	Computed Quantity [US]	Unit of Meas	Mat+Lab+Equip Loaded Unit	Line Extension	Subtotals
C	INTERIORS		***System Subtotal***	92,000.00	GSF	26.19		2,409,820.00
New ES			***Partition Assemblies***					
New ES		1.00	Interior partitions	91,080.00	WallSF	6.00	546,480.00	
New ES		2.00	GWB + mtl furring, int face ext walls		Excluded			
New ES		3.00	Interior glass	10,120.00	WallSF	35.00	354,200.00	
New ES								
New ES			***Door, Frame & Hardware Assemblies***					
New ES		1.00	Door assm, single	105.00	EA	1,400.00	147,000.00	
New ES		2.00	Door assm, dbl	20.00	EA	2,450.00	49,000.00	
New ES								
New ES								

PROGRAMMATIC COST ESTIMATE
Proj Name: NEW ABINGDON E.S.
Project Owner: Arlington Public Schools

FORELLA GROUP, LLC
9495 Silver King Court
Suite A

Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Approved By:	pf	File:	Programmatic	
		Email:	Design	

PROGRAMMATIC COST ESTIMATE		FORELLA GROUP, LLC	Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Proj Name: NEW ABINGDON E.S.		9495 Silver King Court	Approved By:	pf	File:	Programmatic	
Project Owner: Arlington Public Schools		Suite A			Email:	Design	
Project Location: Arlington County, VA		Fairfax, VA 22031-4713			Report Date:	Reference Date Stamp	

Scheme and Location Ref	Uniformat System Heading	Uniformat No. Code	Descriptions and/or Specification Notes	Computed Quantity [US]	Unit of Meas	Mat+Lab+Equip Loaded Unit	Line Extension	Subtotals
E	EQ & FURNISHINGS		***System Subtotal***	92,000.00	SF	7.53		693,120.00
New ES			***Special***					
New ES		1.00	Folding walls	2,016.00	WSF	40.00	80,640.00	
New ES		1.00	Gymnasium equipment	5,040.00	GSF	12.00	60,480.00	
New ES		2.00	Casework, millwork, etc.	92,000.00	GSF	6.00	552,000.00	
F	SPECIAL		***System Subtotal***				Not used	
Z	GENERAL		***Subtotal A-F***					16,148,379.43
New ES		1.00	Field Overhead Incl Phasing Premium				1,614,837.94	
New ES		2.00	Subtotal				17,763,217.37	
New ES		3.00	Main Office Overhead & Profit				1,776,321.74	
New ES		4.00	Subtotal				19,539,539.11	
New ES		5.00	Bonds & Insurance				293,093.09	
New ES		6.00	SUBTOTAL	92,000.00	GSF			19,832,632.20

PROGRAMMATIC COST ESTIMATE			FORELLA GROUP, LLC	Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Proj Name: NEW ABINGDON E.S.			9495 Silver King Court	Approved By:	pf	File:	Programmatic	
Project Owner: Arlington Public Schools			Suite A			Email:	Design	
Project Location: Arlington County, VA			Fairfax, VA 22031-4713			Report Date:	Reference Date Stamp	

Scheme and Location Ref	Uniformat System Heading	Uniformat No. Code		Descriptions and/or Specification Notes	Computed Quantity [US]	Unit of Meas	Mat+Lab+Equip Loaded Unit	Line Extension	Subtotals

[redacted]

PROGRAMMATIC COST ESTIMATE
Proj Name: NEW ABINGDON E.S.
Project Owner: Arlington Public Schools

FORELLA GROUP, LLC
9495 Silver King Court
Suite A

Prepared By:	ia,ja, cy	Job #:	11158.1	Revisions
Approved By:	pf	File:	Programmatic	